

December 12, 1972

Mr. Mark E. Boyden, County Surveyor
Jackson County Court House
Medford, Oregon 97501

SUBJECT: Re-establishment of 1/4 corner located in Township 37 South,
Section 6, Range 1 West and Section 1, Range 2 West, Willamette
Meridian.


PROCEDURE: Due to the extension of the Jackson County Airport runway #14
and the necessary re-location of a drainage canal, the said
1/4 corner would have to be removed. The corner was a 1" iron
pipe situated at the south line of Shultz Road and centerline
of Biddle (re: Range Line) Road. On April 28, 1968 I located
a hub on the range line North 318.50 feet from said corner;
to be used later as a reference to re-set said corner. In
November 1968, I re-set a 1-1/2" x 30" iron pipe for the true
corner on line between the section corners; said pipe falls
on the south bank slope of drainage ditch 'A'. Ditch 'A',
being the name so designated on the F.A.A. plans 1968.

The South 1/16 (3" brass disk) and the North 1/16 (3/4" iron
pipe) along with the 1/4 corner are all on the same line between
the two section corners.

The northeast corner of Donation Land Claim No. 57, Township
37 South, Range 2 West, a 1/2" iron pipe was destroyed also,
but can be re-set from references F.B.A1968-4 City of Medford,
page 10.

To accompany this report are copies of the field notes in
F.B.A1968-4 and A1968-5 City of Medford Surveys.

Respectfully submitted:


C. Lind McBeth, R.L.S. #565
Jacksonville, Oregon

