

SURVEY	NO.	_5038
	110.	<del>-</del> , <del>-</del>

## SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209-250

Survey for:

City of Talent

72-36

Parks Commission Talent, Oregon

Survey by:

Edward A. McGinty, R.S.

Medford, Oregon November, 1972

Location:

S.W. 1/4, Sec. 24 & W. 1/2, Sec. 25

Township 38 South, Range 1 West

Basis of Bearing:

B.C.V.S.A. Survey of Sanitary Sewer

Precedence of Survey:

Alignment of right of way Interstate Highway No. 5 is shown approx. using monuments at North side of Valley Viww and an O.S.H.D. monument found at point "B". (Note: found this line differing slightly by using O.S.H.D. monument on center line.)

From point "B" to point "F" is a retracement of old survey by O.S.H.D. with some of the points prorated in position.

At point "C" found post hole and remains of a 4" x4" wood post right of way marker, set 5/8 inch iron pin.

At point "D" found a 4"  $\times$  4" right of way marker, set 5/8 inch iron pin and replaced post along side.

At point "E" found a 5/8 inch iron pin, a right of way post along side.

From point "F" to "G" is approx. boundary and varies from deed record on bearing, however it appears to be the intent of the deed record to follow this line and agrees closely to portion of old fence recovered along thisline.

Point "G" is set at record from point "H" which is a 5/8 inch iron pin recovered on Survey No. 2025.

PROFESSIONAL LAND SURVEYOR

OREGON
JULY 10, 1983
DWARD A. MCGINTY

