

and chain, enclosed the subject premises, making side ties to Station "Colver" and the S.S.E. corner of DLC #41. Some unrecorded monuments were found near the Westerly boundary of the subject premises which were surprisingly close to the Deed Record ties from the S.S.E. corner of DLC #41. Said monuments, being unrecorded were disregarded, and the Westerly boundary of the subject premises was located by Deed Record ties.

At the Northeast corner of DLC #44, T38SR1W, set a 3/4" x 36" galvanized iron pipe 30" in the ground with a 2" bronze cap stamped:

T38SR1W
1972
DLC NE
COR 44
RS 281

for corner, from which:

A 10" Willow, scribed "RS 281-BT" bears S 47° 25' E, 26.0 feet to the face of the lower blaze;

The Southerly fork of a twin 14" Cottonwood, scribed "RS 281-BT" on one blaze bears S 39° 35' W, 6.7 feet to the face of the blaze.

At the Northwest corner of Donation Land Claim No. 42, Township 38 South, Range 1 West, set a 3/4" x 36" galvanized iron pipe 20" in the ground with a 2" bronze cap stamped:

T38SR1W
1972
DLC NW
COR 42
RS 281

for corner, from which:

A 7" Willow, scribed "RS 281-BT" bears N 51° 15' E, 40.3 feet to the face of the lower blaze;

A 10" Cottonwood scribed "RS 281-BT" bears S 71° 37' E, 42.9 feet to the face of the lower blaze.

From said data, monumented the desired tract as shown on the map to accompany this report.

December 15, 1972

