



JACKSON COUNTY
RECEIVED
FEB 26 1973
SURVEYOR

OREGON
LAND SURVEYOR
G. A. Hoffbuhr

MAP OF SURVEY
LOCATED IN
N.W. 1/4 OF SECTION 4, T. 35S., R. 1 W., W.M.
JACKSON COUNTY OREGON
FOR
LOST CREEK REALTY

J. A. HOFFBUHR, REG. L.S., MEDFORD, OREGON
SCALE: 1" = 200' AUGUST 28 1970
BASIS OF BEARING - SOLAR OBSERVATION
○ = SET 5/8" X 24" IRON REINFORCING PIN
○ = SET 5/8" X 30" IRON REINFORCING PIN FOR WITNESS COR

5104

SURVEY NO. 5104

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Lost Creek Realty
Shady Cove, Oregon

LOCATION: Tract situated in the Northwest One Quarter (1/4)
of Section 4, Township 35 South, Range 1 West,
Willamette Meridian, Jackson County, Oregon.

PURPOSE: To monument the corners of the tract of land
shown on the attached map.

PROCEDURE: The Section Corner common to Sections 4, 5, 8, and
9, could not be found although the four adjacent corners were intact.
The Section Corner was set by double proportionate measurements and
referenced as shown on the attached map. The meander line was also
established from the original field notes, the bearings and distances
being adjusted to conform to the chained distances. There was no
evidence of the original corners.
Basis of bearings -- Solar Observation.

February 22, 1973

J. A. Hoffbuhr
Professional Land Surveyor

