



MAX H. HULL Land Surveying

602 N. W. 5th. Street Grants Pass, Oregon 97526

SURVEY NARRATIVE to comply with Paragraph 209.250, O. R. S.

DATE: March 21, 1973

FOR: Mr. Richard Rhoten
9615 East Evans Creek Road
Rogue River, Oregon

PURPOSE: To partition property in the Southeast 1/4 of Section 10,
Township 35 South, Range 4 West, Willamette Meridian, Jackson
County, Oregon.

PROCEDURE: Starting at a 1" Iron Pipe per Survey 3441, which is on the
South line of the Southeast 1/4 of Section 10 and bears West
914.30 feet from the Southeast corner of said Section 10;
thence using the property deed description bearing and
distances, I Surveyed North 64°04' East 443.00 feet; thence
North 53°04' East 340.00 feet; thence North 40°06' West
121.90 feet at which point I set a 5/8" Iron Rod, from this
point I set a witness corner North 8°47'30" East 524.53 feet;
thence I proceeded North 40°06' West 255.56 feet and set
a 5/8" Iron Rod from which I set witness corners North 40°06'
West 314.23 feet and North 11°47' East 301.46 feet.

Meridian was based on the deed call of "West" on the South
line of the Southeast 1/4 of Section 10.



Max H. Hull

