



NORTH

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Everett L Swain*

OREGON  
JULY 8, 1963  
EVERETT L SWAIN  
759

MAP OF SURVEY  
LOCATED IN  
SEC. 9, TWP. 39 S. R. 1 E., W. B. M.  
ASHLAND, JACKSON COUNTY, OREGON  
FOR

JACKSON COUNTY  
RECEIVED  
MAY 1 1973  
SURVEYOR

**DR. WILLIAM RAMSEY**

EVERETT L. SWAIN, R.L.S.      ASHLAND, OREGON

SCALE: 1"=50'      FEBRUARY 5, 1973

BASIS OF BEARING      N.O.A. TRUE BEARING N-S & SEC. 9

- FOUND MONUMENTS AS SHOWN
- SET 5/8x 24 INCH IRON PIN TAGGED R.L.S. 759

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
OREGON REVISED STATUTES

SURVEY FOR: Dr. William Ramsey  
582 Holly Street  
Ashland, Oregon 97520

LOCATION: Situated in Section 9, Township 39 South, Range 1 East of the  
Willamette Base and Meridian, Jackson County, Oregon.

PURPOSE: To survey a tract of land into three parcels and prepare a legal  
description for each.

PROCEDURE: Tied all street monumentation and other unrecorded monuments to my  
control net. Established the street centerlines after a complete  
analyzation of the entire area. Held the north boundary of Jessels  
Subdivision parallel to the centerline of Holly Street. The "initial  
point" of said subdivision was held for the proper latitude. Surveyed  
the parcels as shown on the accompanying map.

February 5, 1973

Everett L. Swain  
Professional Land Surveyor  
Ashland, Oregon

