

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Mr. Kenneth Cearley
2813 Biddle Road
Medford, Oregon

LOCATION: Tract situate in the Northwest Quarter of
Section 34, Township 37 South, Range 2 West,
Willamette Meridian, Jackson County, Oregon.


PURPOSE: To partition into tracts, describe and
monument the corners of the tract shown on
the attached map.

PROCEDURE: Located Northwest and Southwest corners of
Donation Land Claim No. 78 and determined the mid-point; found
the 1-1/2 inch pipe re Recorded Survey No. 4326 and Recorded
Survey No. 134. The East-West dividing line between the North
and South halves was developed by projecting the line from the
mid-point between the two West corners to the 1-1/2 inch pipe.


It was determined that Recorded Survey No. 1256 used the
existing fence lines on the East and South lines of the tract.
This survey uses record distance to position the East Line and
the above mentioned dividing line for the South Line. The
tract was partitioned as indicated on the attached map.

Basis of bearings--Recorded Survey No. 1256.

May 21, 1973



J. A. Hoffbuhr
Professional Land Surveyor



J. A. Hoffbuhr

