

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Charles Thomas
411 Alpine Way
Talent, Oregon

PURPOSE: To partition Lot 17 and 20, Block 2, of HYDE PARK
SUBDIVISION as shown on the accompanying map.

PROCEDURE: From original block corner monuments found, the
corners of Lots 17 and 20 were established on a
proportional basis. The partition of Lots 17 and
20 was established according to clients instructions.
The 2 inch iron pipe found at the Northeast Corner
of Block 2 has been disturbed. The true position
as determined from other monuments is North 35° 43'
40" East 0.33 feet from said 2 inch iron pipe.
The concrete monument angle point near the South-
east Corner of Block 2 has been destroyed by sewer
construction. The position for this angle point
was determined by holding record angle and distance
from the Southwest Corner of Block 2.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

George Burrell

OREGON
JULY 10, 1964
GEORGE R. BURRELL
638

