

September 10, 1964

1/4 cor. Sec.s 1 & 12, T.39S., R.5 W.W.M.

At the 1/4 corner I find an 18 in. B. Oak O.B.T., bears S.35°W. 52.80 feet, with scar; also a 3/4 in. I. Pipe and 2 B.T.s recently marked:

An 8 in. B. Oak bears S.75°E., 20.0 feet scribed "1/4S12 BT"

A 10 in. B. Oak bears S.15°E., 12.3 feet scribed "1/4S1 BT"

New B.T.s and pipe have tag marked "Lee B. Coon RS 439".

Mag. var. 19°00'E.

Renewal of Sec. cor.s $\begin{array}{c|c} 2 & 1 \\ \hline 11 & 12 \end{array}$ T.39S., R.5 W.W.M.

At corner I find 40 in. W. Oak O.B.T. bears S.10°E. 86.46 feet chopped out, scribing destroyed. A 3/4 in. Iron Pipe with tag mkd. "Lee B. Coon R.S.439" is 0.60 feet South and 0.25 feet East of true position.

To renew I set a 1 1/2"x30" G.I. Pipe with Brass Cap in mound of rocks and scribe:

A 22 in. W. Oak bears N.72°00'W. 61.0 feet (S2 CS BT)

A 26 in. forked Madrone bears N.42°15'E., 79.7 feet (S1 CS BT)

A 40 in. W. Oak bears N.86°30'E., 72.1 feet (S1 CS BT)

Mag. Var. 19°00'E.

Sec. cor. $\begin{array}{c|c} R5 & R4 \\ \hline 1 & 6 \\ \hline 12 & 7 \end{array}$ T.39S., W.W.M.

At the section corner, I find no evidence to substantiate the true location of the corner, which would fall near the middle of a cleared field.



Robert M. Thompson
Robert M. Thompson, R.El. 3683
Deputy County Surveyor
Witnesses: G. Riley
F. Thomas