

5285

December 22, 1969

Renewal of Section cor. common to $\frac{24}{25}$ T. 39 S., R. 5 W.W.M.

At corner I found a 12"x10"x8" Basalt stone with 4 notches on North face and 2 notches on South face, and the following original B.T.:

A 12 inch fir bears N. 83° W., 19.1 ft. dist. to face, with scribing visible.

No evidence of oak B.T. Basalt stone is quite unstable, therefore I removed same and:

At corner I set a G.I. Pipe 30 inches long, 1 1/2 inches in diam., 28 inches in the ground with Brass Cap stamped "T39S " and deposited stone alongside from which the following B.T.s: $\frac{R5W\ 24}{25}\ R4W$

1969

A 16 inch fir, bears S. 89 1/2° W., 40.9 ft. dist. to center of tree, scribed "CS S25 BT".

A 15 inch fir bears S. 54 3/4° W., a dist. of 33.2 feet to center of tree scribed "CS S25 BT".



E. L. Swain
 E. L. Swain, R.S. 759
 Deputy County Surveyor

Witness: J. Lamar