

- ① FOUND ORIG. COR. STONE & O.B.T.'S, IN GOOD CONDITION
- ② 1/4 COR. SEC. 1 ONLY, FOUND ORIG. COR. STONE IN PLACE "1/4" ON N. & S. SIDES, SCRIBE:
8" D. FIR, N88°W, 30.6'; 10" D. FIR, N21°30'E, 13.9', BOTH SCR. "1/4 S 1 BT" (O.B.T.'S BURNT OUT)
- ③ SET 1 1/2" G.I. PIPE, BY PROP. MEAS. FOR 1/4 S 36 ONLY, SCRIBE:
14" D. FIR, S5°00'W, 15.1', "1/4 S 36 BT"
10" D. FIR, N57°E, 28.1', " " "
- ④ SET 1" I. PIPE IN ROOTS OF 14" D. FIR, SCRIBE:
14" D. FIR, S16°00'W, 1.67', "1/6 S 36 3683 BT"
10" D. FIR, N17°00'W, 4.28', " " "
- ⑤ FOUND 1 1/2" I. PIPE & 1 ORIG. O.B.T., NOW 36" B. OAK N45°W, 27.4'
- ⑥ 1/4 S 31 ONLY, FOUND ORIG. O.B.T. TO N.E (GOOD COND.) & COR. STONE, ROLLED OUT OF POSITION.
I SET 1 1/2" G.I. PIPE IN PROPER POS. & RESET STONE ON W. SIDE, SCRIBE:
10" B. OAK, S28°00'E, 19.74', "1/4 S 31 B.T."
- ⑦ SET 1 1/2" G.I. PIPE BY PROP. MEAS. FOR 1/4 S 36 ONLY, SCRIBE:
14" S. PINE, S38°00'W, 23.74', "1/4 S 36 B.T."
18" D. FIR, N27°00'W, 20.35', " " "
- ⑧ SET 1" I. PIPE, SCRIBE:
8" D. FIR, N36°00'E, 4.73', "1/6 S 36 3683 BT"
6" D. FIR, N80°00'W, 5.14', " " "
- ⑨ SET 1" I. PIPE FOR CTR 1/4 COR., SCRIBE:
10" TAN OAK, N36°30'E, 10.6', "C 1/4 S 36 3683 BT"
6" D. FIR, S11°00'E, 5.7', " " "
12" MADRONE, S40°30'W, 26.0', " " "
12" W. OAK, N48°00'W, 18.92', " " "
- ⑩ FOUND ORIG. COR. STONE & ALL O.B.T.'S, IN GOOD CONDITION.
- ⑪ FOUND ORIG. COR. STONE & O.B.T.'S, IN GOOD CONDITION.
- ⑫ FOUND ORIG. COR. STONE, O.B.T.'S TO NE & SE IN GOOD CONDITION; SW O.B.T. NOW DEAD
16" B. OAKS STUB; ALSO FOUND NEW 18" D. FIR B.T.'S TO NE & SW.



SURVEY TO LOCATE BOUNDARIES OF W 1/2 SE 1/4 SEC. 36, T36S, R5W, W. M.

SCALE: 1 INCH = 400 FEET

JUNE, 1962

ROBT. M. THOMPSON

DONE FOR: BROWN BROS. LUMBER CO.
BOX 328, GRANTS PASS, ORE.

NOTE: BEARINGS DETERMINED BY YOUNG & SONS SOLAR COMPASS.

BOUNDARIES OF W 1/2 SE 1/4 MARKED WITH RED PAINTED BLAZES.

