



MAP OF SURVEY
FOR
RAY E. & ELLEANOR ALBERTS

JACKSON COUNTY
RECEIVED
SEP 24 1973
SURVEYOR

LOCATION
LOT 24 BLOCK 3
COLLEGE HILLS ADDITION
NW 1/4 SEC 20 T37S, R1W W.M.
JACKSON CO. OREGON
SCALE 1" = 100' DATE AUG 1973
SURVEY BY LARRY J. FRIAR PLS 961
BASIS OF BEARING SURVEY NO. 4296
O SET 5/8" IRON PIN

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Larry J. Friar
OREGON
JULY 16, 1971
LARRY J. FRIAR
961

SURVEY NO. 5372

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209, 250, O. R. S.

SURVEY FOR: Ray E. Alberts
and Elleanor Alberts
2131 Hill Way
Medford, Oregon

LOCATION Lot 24 Block 3 College Hills Addition
North West ($\frac{1}{4}$) Section 20, Township 37 South,
Range 1 West, Willamette Meridian, Jackson
County, Oregon

SURVEY BY: Larry J. Friar P.L.S. 961
August, 1973

BASIS OF BEARING: Survey No. 4296

PURPOSE: To Monument Parcel as shown on attached map.

PROCEDURE: Recovered the North East and North West
Corners of College Hills Addition found
in Survey No. 4296.

Found a 1" Pipe at the North East Corner
of Block 9, College Hills Addition and
used to Control Location of East Line of
Subdivision.

The Center Line of Spring Street was held
as established in Survey No. 3388.

The Re-established one quarter Corner was
used to Control the West Line.

The Lot and Block Dimensions were then
determined on a proportional basis.

Monuments set and found as shown on the
attached map.

