



JACKSON COUNTY
 RECEIVED
 DEC 31 1973
 SURVEYOR

REGISTERED
PROFESSIONAL
 LAND SURVEYOR
G. W. Plumb
 OREGON
 JULY 12, 1968
 G. W. PLUMB
 862

BEARINGS FROM R S 3766
 ● FND 5/8" IRON ROD UNLESS
 OTHERWISE NOTED
 ○ SET 5/8" X 24" IRON ROD

PROPERTY SURVEY
 SITUATE IN
 NW 1/4 SEC 4 T 35 S R 4 W WM
 JACKSON COUNTY OREGON
 G W PLUMB LAND SURVEYOR
 MEDFORD OREGON NOV 1973
 SCALE 1" = 200'

FND IRON PIPE

FND IRON PIPE

FND BT'S

I PIPE

Survey for Richard P. Faltersack
 275 Fourth Avenue
 Gold Hill, Oregon 97525

Survey by G. W. Plumb
 P. O. Box 904
 Medford, Oregon 97501

Location N $\frac{1}{2}$ Sec. 4, T. 35 S., R. 4 W., W.M., Jackson County, Oregon.

Found two original and three reestablished bearing trees for the corner of Sections 33, 34, 3 and 4. Found 1 $\frac{1}{2}$ " iron pipe for reestablished quarter corner of Sections 33 and 4. Found 5/8" iron rod per R.S. 4923 for west sixteenth corner of Sections 33 and 4. Found iron pipes with B.T.'s per R.S. 121 for the center quarter corner, and the center west sixteenth corner of Section 4. Found two B.T.'s per R.S. 121 for the east center sixteenth corner of Section 4. Found brass cap monument at the reestablished quarter corner of Sections 3 and 4.

Subdivided the north half of Section 4 from these monuments, and set 5/8" x 30" iron rods as shown on the accompanying map.

30 November 1973

