

5587

5587

Survey No. _____

Jackson County Surveyor
Edward A. McGinty
Medford, Oregon

Subject: Re-establishment of the standard 1/4 corner of Section 36,
T38S, R04E, W.M.

Set a 5/8" x 30" I.R. from the B.T.s as described by U.S. Transi-
man, Fred Mensch under instruction dated June 2, 1911 - Group 6 -
and from which bears:

- A Sugar Pine 24" in diameter, S68°W, 64.0 Lks. (B.T.)
- A Fir 7" in diameter, N44°W, 85.0 Lks. (B.T. Dead and Down)

A SurvKAP was set atop the I.R. that was stamped:

WEYERHAEUSER

SC		
1/4 36		31
1973		
ORLS 661		

and from which bears:

- A 'W' nail set in the base of a Fir 7" in diameter that lies
S65°E, 23.0 Lks. distance.
- A 'W' nail set in the base of a Fir 4" in diameter that lies
S58°W, 32.1 Lks. distance.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Everett J. Scott

OREGON
JULY 10, 1964
EVERETT J. SCOTT
661

JACKSON COUNTY
RECEIVED
JAN 29 1974
SURVEYOR