

Survey No. 5588
~~3388~~

Jackson County Surveyor
Edward A. McGinty
Medford, Oregon

Subject: Re-establishment of the standard corner common to Sections
25 and 36, T38S, R04E, W.M.

Set a 5/8" x 30" I.R. from the B.T.s as described by U.S. Transit-
man, Fred Mensch under instructions dated June 2, 1911 - Group 6 -
and from which bears:

A Fir 30" in diameter, S49°W, 70.0 Lks. (B.T.)
A Fir 20" in diameter, N75°W, 48.0 Lks. (B.T. Dead and Down)

A SurvKAP was set atop the I.R. that was stamped:

WEYERHAEUSER

T38S R4E
25 | 30
36 | 31 SC
1973
ORLS 661

and from which bears:

A 'W' nail set in the base of a Fir 6" in diameter that lies
East, 37.2 Lks. distance.
A 'W' nail set in the base of a Fir 7" in diameter that lies
S48°E, 32.5 Lks. distance.
A 'W' nail set in the base of a Fir 6" in diameter that lies
N80°W, 101.0 Lks.

