

5589

5589

Survey No. _____

Jackson County Surveyor
Edward A. McGinty
Medford, Oregon

Subject: Re-establishment of 1/4 corner common to Sections $\frac{9}{16}$ T40S,
R04E, W.M.

Replaced described stone (14"x12"x8") with a 5/8" x 30" I.R. upon
which was set a SurvKAP that was stamped:

WEYERHAEUSER

1/4 $\frac{S9}{S16}$

1970
ORLS 686

from which I found the original B.T.s

A Yellow Pine 18" in diameter, bears S15⁰E, 26 Lks. (now dead
and down)

A Yellow Pine 10" in diameter, bears N17⁰W, 32 Lks. (dead top)

No additional reference trees were established as a mound of stone
was built up around the corner.

