



MAP OF SURVEY  
FOR  
JACK R. STATER

Located in  
The S.W. 1/4 of Sec. 20, T. 38 S., R. 2 W., W.M.  
Jackson Co., Oregon  
Scale: 1" = 300'  
Basis of Bearing - Solar Obs.  
Survey by: L. J. Friar P.L.S. 961  
Feb. 22, 1974  
• Set 5/8" iron pin  
• Set 3/4" iron pin

20 21  
29 28

FD. 1" G.I. PIPE WITH CO. SURVEYOR'S BR. DISK

FD. 1" G.I. PIPE PER CO. SURVEYOR'S RE-ESTAB. NOTES DATED 1936

FD. 1" G.I. PIPE WITH CO. SURVEYOR'S BR. DISK

REGISTERED PROFESSIONAL LAND SURVEYOR

*Larry J. Friar*

OREGON  
JULY 16, 1971  
LARRY J. FRIAR  
961

SURVEY NARRATIVE TO COMPLY WITH O. R. S. 209.250

SURVEY FOR: Jack R. Stater  
4155 Sterling Creek Road  
Jacksonville, Oregon

LOCATION: The S. W.  $\frac{1}{4}$  of Section 20, Township 38 South,  
Range 2 West, Willamette Meridian, Jackson  
County, Oregon.

PURPOSE: To Monument and Describe two Parcels of land  
in the S. W.  $\frac{1}{4}$  of Section 20, as shown on the  
attached map.

PROCEDURE: Ran a closed traverse around the section, and  
tied in all of the existing section corners  
and  $\frac{1}{4}$  section corners, as shown on the attached  
map.

The North  $\frac{1}{4}$  Corner was set on proportionate  
distance after a thorough search failed to  
locate the original corner position.

The Section was subdivided and the two Parcels  
monumented as shown on the accompanying map.

Electronic Distance Measuring Equipment and  
1 second Theodolite was used on this Survey.

DATE: March 20, 1974



Larry J. Friar  
Professional Land Surveyor

