

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 AND REPORT OF COMMISSIONERS
TO COMPLY WITH PARAGRAPH 105.720, OREGON REVISED STATUTES.

Survey for: Arthur D. & Lorraine Savage, 5596 Griffin Lane, Medford, Oregon.
and
Lewis L. & Fredna Dewett, 6452 Blackwell Rd., Central Point, Oregon.

Survey by : Charles H. Hurst, L.S.
23 North Ivy Street
Medford, Oregon 97501

Bearing : Based on the meridian for Survey No. 721 on file in the office
of the Jackson County Surveyor.

Purpose : To monument and define the line between Government Lots 1 & 2,
Section 15, Township 38 South, Range 2 West of the Willamette
Meridian, Jackson County, Oregon, under provisions of Circuit
Court order No. 72-1378-E dated February 26, 1974.

Procedure

Distances were measured utilizing a combination of a 200 foot calibrated steel
tape and an electronic distance measuring device. All angles were measured
with a six second theodolite and turned a minimum of 4 times. Open ties were
made to the quarter corner common to Sections 10 and 15 and the northeast
corners of Sections 10 and 14.

The southerly boundary of the SE 1/4 of Section 15 was measured and checked
against Survey No. 4278 and rechecked by computation through hubs set during
the course of said Survey. All remeasurements are in very close agreement
with this former work, subject to a small bearing rotate to compensate for
slightly different meridians.

The line between Government Lots 1 & 2 was monumented by 5/8" iron pins and
glo-top stakes were set on the true line at approximately 50 foot intervals.

Commissioners Affidavit

I, Charles H. Hurst, do hereby certify that having been appointed a commissioner,
I have entered upon the land of the parties involved and have established and
marked on the ground by proper marks and monuments, the boundary line as ascer-
tained by the Court, namely the line between Government Lots 1 & 2, Section 15,
Township 38 South, Range 2 West of the Willamette Meridian, Jackson County,
Oregon.

Charles H. Hurst

Commissioner

I, Frank Stallings, do hereby certify that having been appointed a commissioner,
I have entered upon the land of the parties involved, and have assisted in estab-
lishing and marking on the ground by proper marks and monuments, the boundary
line as ascertained by the Court, namely the line between Government Lots 1 & 2,
Section 15, said Township and Range, and that I have discharged my duties as a
chainman faithfully and to the best of my ability.


Frank Stallings

Commissioner

I, Verlyn D.B. Thomas, do hereby certify that having been appointed a commissioner,
I have reviewed the procedure and field notes of said survey and find them correct
to the best of my knowledge and belief.

Verlyn D.B. Thomas

Commissioner



Charles H. Hurst

