



JACKSON COUNTY  
RECEIVED  
AUG 23 1974  
SURVEYOR

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Charles H. Hurst*  
OREGON  
OCTOBER 30, 1958  
CHARLES H. HURST  
483

APR 17 1974  
5775

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
OREGON REVISED STATUTES

Survey for: Sherman A. & Bonnie A. Browning  
4762 Dark Hollow Road  
Medford, Oregon 97501

Survey by : Charles H. Hurst, L.S.  
23 North Ivy  
Medford, Oregon 97501

Meridian : Based on that determined for Survey No. 721

Purpose : To define the location of a portion of the westerly boundary of DLC 49 and reset the northwest corner of DR 596-225 on said boundary.

Procedure

This survey was performed utilizing EDM equipment and a six second theodolite.

The location of said DLC line was determined from the SSW corner of said Claim to a 5/8" iron pin set for the deed record "L" corner during the course of Survey No. 3317.

Evaluation of Survey No. 3317 was made with respect to independently determined positions for the SSW and WSW corners of DLC 49 and found in very close agreement. Additional consideration was made against old deeds including DR 22-410 and 44-197.

Accordingly, it was determined that said "L" corner, as presently set, could be held for departure thus controlling the direction of the DLC line. Line monuments were set at random distances along said line as shown on the attached plat.

The 1/2" iron pipe mentioned in DR 596-225 was held for latitude and a 5/8" iron pin was set for the true northwest corner location of said deed. According to Mr. W.W. Martin, 4618 Dark Hollow Road, this pipe was personally set by Fehl, Martin assisting, intended to be on the DLC line and marking the northwest corner of the tract presently owned by the Brownings.

No information is available relative to the 1/2" iron pipe found near the SSW corner of DLC 49.

April 17, 1974

