

PREPARED BY THE JACKSON COUNTY SURVEYORS OFFICE
ON AUGUST 28, 1974
E.A. MCGINTY, COUNTY SURVEYOR
BY E.B. GRAHAM, DEPUTY
BASIS OF BEARING - JACKSON COUNTY CONTROL NET

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Edward B. Graham

OREGON
JULY 22, 1974
EDWARD B. GRAHAM
NO. 1008

JACKSON COUNTY
RECEIVED
OCT 3 1974
SURVEYOR



SCALE: 1" = 20'

○ — Set 5/8" x 30" Iron Pin



SURVEY FOR JACKSON COUNTY AIRPORT
SHOWING LEASE PROPERTY LOCATION
IN THE NE 1/4 OF SEC. 12, T.37S., R.2 W.W.M.
JACKSON COUNTY, OREGON

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: Jackson County Airport

LOCATION: N.E. 1/4 of Section 12, Township 37 South, Range 2 West, Willamette Meridian, Jackson County, Oregon.

PURPOSE: To locate, monument and describe two tracts of land at the Jackson County Airport for lease purpose.

DATE: August 28, 1974

BY: Jackson County Surveyor's Office
E.A. McGinty, County Surveyor
E.B. Graham, Deputy Surveyor

PROCEDURE: A copy of the platted but unrecorded Subdivision "A" was obtained from the City of Medford. Since existing lease descriptions were written from this plat, the basic intent of Subdivision "A", as set down by the City of Medford, was held. Primary consideration was alignment orientation. Field ties to found monuments revealed sufficient conformity with existing improvements in relation to dimensions shown on the unrecorded plat to accept some of the monuments for control. The information regarding size and approximate location for the intended tracts was provided by the Airport Manager. The resulting tract layout is shown on the attached map which by reference becomes a part of this narrative. A field tie to the East Quarter corner of Section 12, Township 37 South, Range 2 West, Willamette Meridian and ties to the Jackson County Control Net (1968). For basis of bearing were accomplished using a One-second Theodolite and Electronic distance measurement.



Edward B. Graham

