



NOTE:
SEE DECREE
No. 74-2008-L-2

SHERMAN M. SPEARS, SR.
RE: INSTRUMENT NO.
71-06119

PROPOSED BOUNDARY
LINE AGREEMENT

O. C. RICHEY

NORTH

JACKSON
RECEIVED
APR 30 1975
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Everett L. Swain

OREGON
JULY 8, 1966
EVERETT L. SWAIN
759

MAP OF SURVEY

LOCATED IN
D.L.C. No. 41, IN SEC. 5, TWP. 38S., R. 1W.W.M.
JACKSON COUNTY OREGON
FOR

DANIEL R. CAILLIER

EVERETT L. SWAIN, R.L.S.

ASHLAND, OREGON
JUNE 28, 1973

SCALE: 1" = 30'
BASIS OF BEARING

RECORDED SURVEY No. 2542

- FOUND MONUMENTS AS SHOWN
- SET 5/8 x 24 INCH IRON PIN WITH ALUMN. CAP

FD. 5/8" I. PIN
RE:
R.S. No. 2542

REVISED APRIL 20, 1973

Revised SEPTEMBER 1, 1973

6003

6003

SURVEY NO. ~~6003~~

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Daniel R. Caillier
94 West Glenwood Road
Phoenix, Oregon 97535

LOCATION: Situated in Donation Land Claim No. 41 in Section 5, Township
38 South, Range 1 West of the Willamette Base and Meridian,
Jackson County, Oregon.

PURPOSE: To survey, monument and prepare a legal description for that
tract of land as shown on the accompanying map per clients
request.

PROCEDURE: Located the survey monuments shown on Recorded Survey No. 2542.
From these monuments established the west boundary line of
Donation Land Claim No. 41. Extended the Donation Land Claim
line to intersect the northerly side of a 40 foot private road
known as West Glenwood Drive to satisfy the intent of the
original description furnished by the client. Established
a portion of the northeasterly boundary along an existing
fence line for the purpose of a boundary line agreement. For
a court settlement see Circuit Court Decree No. 74-2008-L-2.
The remainder of the tract was surveyed as shown on the
accompanying map.

April 28, 1975

Everett L. Swain
Professional Land Surveyor
Ashland, Oregon

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Everett L. Swain
OREGON
JULY 8, 1966
EVERETT L. SWAIN
759

JACKSON COUNTY
RECEIVED
APR 30 1975
SURVEYOR

55 T 38.1W