

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

Survey for: **John and Maxine E. DeYoung**
939 Thompson Creek Road
Applegate, Oregon 97530

Survey by : **Charles H. Hurst, L.S.**
23 North Ivy
Medford, Oregon 97501

Bearing : The meridian for the Thompson Creek Road "P" line
between Stations 54+52.56 and 57+58.06 subject to
a rotation of 0°00'31" counter-clockwise from
record.

PROCEDURE

Closed circuit traverse utilizing EDM equipment with open ties to the northeast corner of Section 28 and the east, west and south quarter corners thereof.



The location of the north quarter corner was computed on the basis of data furnished from the field notes relative to Survey No. 3607.

The 1" axle shaft set for the northeast 1/16 corner common to Sections 21 and 28 is suspected to have been set during the course of a survey made by the Jackson County Surveyor in 1942, said survey being entered on page M-37 of Official Surveys.

Since no official centerline exists for Thompson Creek Road, the easterly boundary of the road is shown as described in the official survey of record and OR 69-05969 subject to a bearing rotation of 0°03'49" clockwise from said axle shaft.

The 1.618 acre tract is to be a revision of OR 72-14797 as shown.

May 29, 1975



Charles H. Hurst

