

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 O.R.S.

SURVEY FOR: WILLIS STIEHL
Foodland Farms
Rogue River, Oregon


LOCATION: In the Southwest Quarter of the Northwest Quarter of Section 15, Township 36 South, Range 4 West of the Willamette Meridian, Jackson County, Oregon.

PURPOSE: To survey and monument those parcels of land shown on attached plat.

PROCEDURE: Beginning at a 5/8" diameter iron rod monumenting the Northwest 1/16 corner per R.S. #5583 of the Jackson County Survey Records; thence I run North $89^{\circ}32'14''$ West along the North line of the Southwest Quarter of the Northwest Quarter of Section 15, 297.89 feet, at which point I set a 5/8" x 30" iron rod; thence I run South $00^{\circ}24'08''$ East 146.60 feet, at which point I set a 5/8" x 30" iron rod; thence I return to the Northwest 1/16 corner per R.S. #5583 of the Jackson County Survey Records and run South $00^{\circ}09'53''$ West along the East line of the Southwest Quarter of the Northwest Quarter of Section 15, 142.26 feet, at which point I set a 5/8" x 30" iron rod; thence I run South $89^{\circ}37'36''$ West 140.01 feet, at which point I set a 5/8" x 30" iron rod; thence I run South $17^{\circ}07'28''$ West 176.13 feet to the Northerly right of way line of the future extension of Valley View Drive, at which point I set a 5/8" x 30" iron rod; thence I run South $48^{\circ}00'43''$ West 50.00 feet to the Southerly right of way line of the future extension of Valley View Drive, at which point I set a 5/8" x 30" iron rod.

All bearings per recorded survey No. 5583 of the Jackson County Survey Records.

Survey was executed with a Wild T-16ED Transit Theodolite and 200.00 foot steel chain.



June, 1975