

Survey No. 6546

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250.

FOR: Boise Cascade Corporation
P. O. Box 100
Medford, Oregon, 97501

PURPOSE: To re-monument the corner position established by Joseph S. Gawron and Rollin Aanrud B.L.M. cadastral surveyors on survey approved on July 12, 1966 for the Center-South one-sixteenth Section corner of Section 7, Township 33 South, Range 1 East of the Willamette Meridian in Jackson County, Oregon.

PROCEDURE: Found the original Gawron-Aanrud corner monument damaged and dislodged from its original position.
Set a 3/4" x 36" galvanized iron pipe with a 2" bronze cap stamped:

C
S 1/16 | S7
C
R.P.L.S. 281
1976, 34" in the ground

for corner, from which:

The 14" Douglas Fir (with healed blaze) bears North 18 1/4° East, 13.86 feet (Record = North 22° East, 13.86 feet) to the center of the tree.

The 8" Douglas Fir (with healed blaze) bears North 77 1/2° West, 29.04 feet (Record = North 75° West, 29.04 feet) to the center of the tree.

For a basis of bearings, utilized the Gawron-Aanrud 1966 survey for the "North-South" centerline of Section 7 of South 2° 17' West.

November 24, 1976

