

SURVEY NO. 6607

SURVEY NARRATIVE TO COMPLY WITH O.R.S.209.250

FOR: E.J. Fordyce and Assoc.
1175 Court St.
Medford, Oregon

PURPOSE: To monument the tract described in Document No. 66-06581
of the Official Records of Jackson County, Oregon.

PROCEDURE: The Point of Beginning of said tract was established
using deed record distance along the North line of D.L.C.
No. 39 from the S.E. Cor. of D.L.C. No. 38 as presently
monumented. The record angle of 90° 00' was held at the
intersection of the West tract line and the D.L.C. line.
Record distance was then used Northerly to establish the
point of beginning. The Northeasterly boundary of said
tract was established from the present control monuments
found along Corona and Hilton Streets, allowing for a
100 foot radius curve at the centerline intersection of
said Streets.

