


SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Loren E. Messenger
160 Reiten Drive
Ashland, Oregon

PURPOSE: To partially monument and fully describe a tract within the remaining Messenger ownership (Deed Volume 567, Page 470 less Deed Volume 590, Page 397) being located in the East-half of Section 24, T39SR1E, W.M.

PROCEDURE: Utilizing E.D.M. equipment, enclosed the subject tract by random traverse, tying to monuments set on Recorded Survey No. 1235 and Reiten Drive monuments shown on the Official plat of CLAYTON CREEK MOBILE HOME ESTATES SUBDIVISION. The bearing control utilized on Recorded Survey No. 1235 was rotated 0° 01' 30" counter-clockwise and the Southerly and Westerly boundaries of the subject property were determined at Deed Record positions. From said data, monumented the Northerly boundary of the subject premises as shown on the annexed map.

August 5, 1977



56-730-1 P.L. 122