


6918

DON HUNTLEY


J. NORRIS



NOTE:
 ○ INDICATES 5/8" I. ROD SET
 ● INDICATES MONUMENTS FD. AS SHOWN
 BEARINGS ARE BASED ON SURVEY 6400.

6918

F-2



RICHARD L. TEMPLIN
 CONSULTING ENGINEER

PLAT PRELIMINARY SURVEY
 DON HUNTLEY PROPERTY
 LOCATED IN
 NE 1/4 of SECTION 4, T. 35 S, R. 3 W, W.M.
 JACKSON COUNTY, OREGON

SURVEYED FOR: MR. DON HUNTLEY
 SCALE: 1" = 100'

ROGUE RIVER, OREGON
 SEPTEMBER 2, 1977

FD. 3/4" I. PIPE PER CS 2922



RICHARD L. TEMPLIN
CONSULTING ENGINEER

6918

321 NORTHWEST A STREET
GRANTS PASS, OREGON 97526

REGISTERED ENGINEER OREGON
REGISTERED LAND SURVEYOR CALIF.

September 2, 1977

TEL. (803) 476-7114

SURVEY NARRATIVE

Location: NE $\frac{1}{4}$ of Section 4, T. 35S., R. 3W., W.M., Jackson County, Oregon.

Surveyed For: Mr. Don Huntley, 598 Covered Bridge Road, Rogue River, Oregon.

Purpose: To run a reference line in near proximity of the East line of the Don Huntley property.

I begin this survey at the Section corner common to Sections 3, 4, 33 and 34 which is monumented with a 2" diameter iron pipe; thence I traverse S 89°55' 50" E, 2326.12 feet to a point which is monumented with a 5/8" diameter iron rod per survey CS 6400; thence from the position for the E1/16 corner I run South, 272.94 feet at which point I set a 5/8" diameter iron rod; thence I run on a reference line South and set a 5/8" diameter iron rod 1300.0 feet from the E1/16 corner. The reference line is not purported to be the 1/16th line, but to provide information to adjoining property owners as to the location of an existing fence so that the position of the true property line may be resolved.

Bearings are based on survey C.S. 6400.

This survey as executed with a T16-ED Theodolite and a Geodometer-12 electronic measuring instrument.

