

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

Survey for: Paul K. Richardson
1080 Dunlap Road
Jacksonville, Oregon 97530

Survey by : Charles H. Hurst
304 South Holly
Medford, Oregon 97501

Meridian : Based on Survey No. 3033

Purpose : To locate a portion of the physical centerline of Dunlap Road
and monument a 25 foot offset line therefrom.

Procedure



Utilization of transit, tape and EDM equipment. The deed corner set by local residents for the N 1/16 corner was found in error and reset on the basis of the 1909 field notes from the original witness tree scribed by surveyor Elksnat.

This corner has been accepted by local residents and held as the true 1/16 corner. However, having been instructed to hold the line running North therefrom as the section line, this survey does not necessarily indorse said corner or line in the absence of verification.

The northeast corner of tract described in O.R. 76-04828 was held 120 feet Northerly from the deed 1/16 corner to preserve the integrity of intent by local residents who surveyed and monumented the corners of said tract.

The bearing shown for the northerly boundary of Section 32 was derived from Survey No. 3424 by direct tie to monuments set during the course of said survey.

May 20, 1977



Charles H. Hurst

