



SURVEY NO. **7062**

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
OREGON REVISED STATUTES

SURVEY FOR: Jack Selk  
1333 Applegate Road  
Jacksonville, Oregon 97539



LOCATION: Northeast one-quarter (1/4) of Section 21,  
Township 38 South, Range 3 West, Willamette  
Meridian, Jackson County, Oregon

PURPOSE: To survey, monument, and describe three  
parcels as shown on the attached map as per  
client's request

PROCEDURE: Using Recorded Survey No. 2351 and 3422 as control  
for this survey, tied in existing monuments as shown. The average  
existing centerline of China Gulch Road was used to determine the  
Southwesterly boundary of the subject tract. There was some ques-  
tion as to the intent of the bearing on the South line of the subject  
tract. From a field inspection and a legal description call of  
159.0 feet along the Easterly right of way line of China Gulch Road  
(which measures 159.72 feet as shown on map), it was decided to  
use the bearing of South 71° 35' 00" West as measured rather than  
record South 70° West.

Basis of bearing--Recorded Survey No. 3422

January 4, 1978



Richard L. Bath  
Professional Surveyor, Inc.