

7262

SURVEY NO. _____

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Upper Rogue Land and Cattle Co.
P.O. Box 1151
Shady Cove, Oregon 97539

PURPOSE: To subdivide sections 25 and 31 and monument the corners of the clients ownership as shown on the accompanying map.

PROCEDURE: Random traverses were initiated utilizing a Franke 20" Theodilite and a H.P. 3805 Dist. Meter, from which all section corners of control were tied. The interior sectional corners were then calculated and established from random traverse stations.

As no evidence could be found for the original 1/4 corner to sections 25 and 26, the proportional position was established and monumented as shown.

