



SCALE 1" = 30'
Basis of Bearings R.S. 3995

LEGEND

- = Set 5/8" x 24" Iron Pin
- = Fd. mon. as shown



REGISTERED
PROFESSIONAL
LAND SURVEYOR

George Burrell

OREGON
JULY 10, 1964
GEORGE R. BURRELL
638

MAP OF SURVEY

Located in Lot 1 Blk. 2 PIERCE SUB.
In the N.E. 1/4 Section 21, T37S, RIW

For: REX JOHNSON

By: Geo. Burrell, Surveyor, 7/25/78

SURVEY NO. 7360

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Rex Johnson
3550 Lone Pine Road
Medford, Oregon

PURPOSE: To monument the tract described in Document No. 76-01350
of the Official Records of Jackson County, Oregon.

PROCEDURE: Street right of way control was held in accordance with
Recorded Survey No. 3995 using the monuments found as
shown on the accompanying map.

The West boundary of said tract was originally established
by Recorded Survey No. 2892, and is superior to the tract
herein monumented. However, the original monuments found
have been disturbed by construction. I reestablished said
West boundary by holding deed record distance West from
the N.E. cor. of D.L.C. No. 63 and holding right angles
to the line connecting the 1/4 cor. to Sections 16 and 21
and the N.E. cor. of D.L.C. No. 63. The South boundary
of said tract was established by holding deed record distance
South and parallel to Lone Pine Road right of way as outlined
above.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

George R. Burrell

OREGON
JULY 10, 1964
GEORGE R. BURRELL
638

