

Survey Narrative to comply with Oregon State Laws.

Survey for: Chas. E. Rose

By: Edward A. McGinty

BASIS OF BEARING:

Solar observation, approx. on center line of Pierce Road and south line of Section 21.

PRECEDENCE OF SURVEY:

Determined center line of Pierce Road and Spring Street from previous records which agree closely to existing Roads. Used proportional measuring along Pierce Rd. Found some discrepancies in original Sub-div. one of them indicates possible angle point at Aloha St and Brookdale Rd. intersection or possible error in record distance along west line of lot 6, Blk. 9 of Pierce Sub-div.

Tied in South, West and North 1/4 corners and Northwest, southwest section corners in Section 21.

Fences along Brookdale for fifty feet somewhat irregular, shown on map.



Edward A. McGinty Oct 20, 1955

