

SURVEY NO. 7593

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: WAGLER LOGGING
3447 BURSELL ROAD
CENTRAL POINT, OREGON

LOCATION: S.W. 1/4 SECTION 20 T36S R3E
WM JACKSON CO. OREGON.

PURPOSE: TO MARK NEW BEARING TREE AT THE
SW 1/16 CORNER TO REPLACE LOGGED
B.T.

PROCEDURE: FOUND GENERAL LAND OFFICE BRASS
CAP STAMPED S.W. 1/16, S 20 1956,
ON 1 INCH DIA. IRON PIPE IN STONE
MOUND FROM WHICH:

A FIR 18 INCHES IN DIA. BEARS
S 65° W 48.8 FT. OLD B.T.

A FIR STUMP (SAWN) 24" IN DIA.
BEARS S 53° E 33.7 FEET OLD B.T.

A FIR 12" IN DIA. BEARS N 65° E
34.0 FEET SCRIBED SW 1/16 S 20
B.T. NEW B.T.

THE BEARING AND DISTANCE TO THE
NEW B.T. WERE TAKEN TO THE CENTER
OF THE TREE AT ROOT CROWN.

DATE: JANUARY 12, 1979

FRIAR - MOFFIT SURVEYING CO.

