

7618



WEST FORK GRIFFIN CR. RD.

N33°58'45"E ± 7.5'

Δ = 87°52'57"
R = 130'
L = 199.40'

N53°54'12"W 15.08'

Δ = 68°48'54"
R = 90'
L = 108.09'

FOUND 1" PIPE MARKING
THE 1/4 SECTION CORNER

8

N89°38'57"E 1335.06'
1060.13'

FOUND 1 1/2" PIPE MARKING
THE CTR. 1/4 COR. SEC. 9

N89°38'57"E 1335.06'

C.W. 1/16

Δ = 20°31'46"
R = 230'
L = 82.41'

N14°54'42"E 167.21'
170.29'

Δ = 12°04'35"
R = 270'
L = 56.91'

N06°27'31"E 32.02'

Δ = 15°19'25"
R = 180'
L = 48.14'

Δ = 31°56'01"
L = 100.32'

N05°37'04"W 115.93'
25'
N25°28'30"W 88.00'

7618

LEGEND:

- = FOUND MONUMENT AS SHOWN.
- = SET 5/8" PIN WITH PLASTIC CAP STAMPED MOFFIT PLS 944

BASIS OF BEARINGS:

SURVEY NUMBER 5744



PLAT OF SURVEY
FOR
THOMAS PITTOCK
BEING IN THE WEST ONE-HALF
OF SECTION 9, T.38S., R.2W., W.M.
JACKSON CO. SCALE: 1"=100'
OREGON DATE: JAN, 1979
PREPARED BY: FRIAR-MOFFIT SURVEYING



7618

(1400) S9 38 2W

7618

SURVEY NO. _____

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: THOMAS PITTOCK
1014 WEST TENTH STREET
MEDFORD, OREGON 97501

LOCATION: BEING IN THE WEST ONE-HALF (1/2)
OF SECTION 9, TOWNSHIP 38 SOUTH,
RANGE 2 WEST, WILLAMETTE MERIDIAN,
JACKSON COUNTY, OREGON.

PURPOSE: TO ESTABLISH AND MONUMENT A LINE
ALONG AN EXISTING ROAD. A PORTION
OF SAID LINE WILL BECOME A FUTURE
PROPERTY LINE.

PROCEDURE: USING CONTROL ESTABLISHED DURING
SURVEY NO. 5744, I RAN A TRAVERSE
FROM THE WEST ONE QUARTER OF
SECTION 9 TO THE CENTER ONE QUARTER
OF SECTION 9. A TRAVERSE WAS THEN
RAN ON SAID EXISTING ROAD. THE
WESTERLY LINE OF SAID ROAD IS THE
LINE SHOWN ON THE ATTACHED MAP.

DATE: JANUARY, 1979

FRIAR-MOFFIT SURVEYING CO.

