


(Copy of Field Notes transmitted to County Surveyor August, 1956 )  
August 16, 1956



*Spec Cor Book*

Mr. John White  
County Surveyor  
Courthouse  
Grants Pass  
Oregon

Dear Sir:

The south line of Section 12, T. 37 S., R. 5 W., W. M. was surveyed at the request of the Josephine County Court to determine timber trespass of county owned timber. A random line was run east from the corner common to sections 11, 12, 13 and 14 to the corner common to sections 7, 12, 13, and 18, falling 33.8 feet north of the latter corner. The following notes are applicable to a straight line connecting the two section corner with the quarter corner not being found and therefore set by single proportion.

- Set rock 8x10x14 inches for the corner of sections 11, 12, 13 and 14 from which :
  - Original B.T. , a Fir 14 ins. in diam. bears N 25° W , 13.2 feet distant with scribble visible- dead and down.
  - Original B.T. , a Madrona sprout bears N 29½° E, 13.2 feet distant- no marks.
  - Original B.T. , A Madrona sprout bears S 57° W, 25.1 feet distant- no marks.
  - New B.T.- A fir, 14 ins in Diam. bears S10°10' W , 23.8 feet distant marked "S14RE3024BT"
  - New B.T.- A fir, 16 ins in diam. bears N 51°35' W, 25.5 feet distant marked "S11BTRE3024".
  - New B.T.- A Fir, 9 ins. in diameter bears N 11°55' E, 34.8 feet distant marked " S12RE3024BT"
  - New B.T.- A Fir, 28 ins. in diam. bears S 6°00' E, 90.0 feet distant marked "S13RE3024ET"

East on true line between Sections 12 and 13

2655.4 feet Set 18 x 13 x 6 ins. stone marked "1/2" on north face for Quarter Corner at single proportionate distance from which:

- A Fir, 18 ins. in diam. bears S 10° E, 38.7 feet distant marked "1/2 S13RE3024BT"
- A Fir, 22 ins. in diam., bears N 34° W , 14.0 feet dist. marked "1/2 S123024BT"

3983.1 feet Set stone at single proportionate distance for E 1/16 th corner from which:

- A Fir, 16 ins. in diam., bears S 54°05' W, 28.6 feet dist., mkd. "E1/16RE-3024BT"
- A Fir, 24 ins. in diam, bears N39°55' W, 34.8 feet dist. mkd. "E1/16RE3024BT"

5310.8 feet Found 2" diam iron pipe mkd. "RS33" for corner common to sections 7, 18, 12 and 13 from which:

- Original B.T. - A fir, 30 ins. in diam. bears S 8° W, 12.0 feet distant , blaze healed.
- Original B.T. - A Fir, 18 ins. in diam. bears S 45° E, 6.7 feet dist., blaze healed.
- New B.T. - A Fir, 24 ins. in diam. bears N 79°35' E , 24.7 feet dist. (RS33)
- New B.T. - A Fir, 18" in diam. bears N62½° W, 46.0 feet distant (RS33)

*R. L. Templin Jr.*