

7872

1/4 22 FND JACK. CO. BCIP RE-ESTAB  
27

COUNTY

COUNTY

1332.50

ROAD

SHALE CITY

(RECORD DISTANCE = 2665.11)

CN 1/16 - 9" W. OAK N 49°08' E, 17.20'  
6" W. OAK S 18°37' W, 23.76'  
BOTH TREES SCRIBED 'CS-BT'

NW-NE  
SW-NE

SCALE 1" = 300'

APPROXIMATE

PRIVATE

80°45'03" W  
657.95

COUNTY

WITNESS COR.  
ONLY

APPROXIMATE &  
DEAD INDIAN ROAD

674.55

C 1/4 FND 1" IRON PIPE  
(GALVANIZED)

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 8, 1966  
JERRY R. SWANSON  
760

MAP OF SURVEY  
FOR  
JACKSON COUNTY-PROPERTY MANAGEMENT  
SEC. 27, T. 38S., R. 2E., W. M.

JACKSON COUNTY  
RECEIVED  
JUN 21 1979  
SURVEYOR

SURVEYED BY: JACKSON COUNTY SURVEYOR'S  
OFFICE MEDFORD, OREGON

JUNE 20, 1979

JERRY R. SWANSON, DEPUTY  
C.S. PROJECT NO. 79-12

LEGEND

- SET 5/8" x 30" IRON RE-BAR  
BASIS OF BEARING - R.S. NO. 6654
- ⊙ FOUND MONUMENT AS DESCRIBED

7872

38 25 27

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: Jackson County - Property Management  
County Courthouse  
Medford, Oregon 97501

SURVEY BY: Jackson County Surveyor's Office, Project No. 79-12

PURPOSE: To monument the Center North Sixteenth Corner and the Easterly property line of a portion of the Southeast Quarter (SE $\frac{1}{4}$ ) of the Northwest Quarter (NW $\frac{1}{4}$ ) of Section 27, Township 38 South, Range 2 East, Willamette Meridian, Jackson County, Oregon, as shown on the accompanying map of survey.

PROCEDURE: A line was ran between the North Quarter Section Corner and the Center Quarter Section Corner of said Section 27, the Center North Sixteenth Corner was set at the mid-point and the North-South Centerline of said Section was ran to a Witness Corner set northerly of the Dead Indian Road. Corners used for the control of this survey were found as described in R.S. No. 6654 which was both the basis of this survey and basis of bearing used for this survey.

CORNERS ESTABLISHED BY THIS SURVEY: The Center North Sixteenth Corner was set using a 5/8" x 30" iron rebar exposed two inches, with attached yellow plastic plug marked "Jackson C.S.", from which

- a 9" White Oak bears N 49°08' E, 17.20 feet,
- a 6" White Oak bears S 18°37' W, 23.76 feet, both trees scribed "C S BT"

A witness corner was set northerly of Dead Indian Road per the attached map, a 5/8" x 30" iron rebar with attached yellow plastic plug marked "Jackson C.S."

EQUIPMENT USED FOR THIS SURVEY: Kern DKM<sub>2</sub> one-second Theodolite, Geodometer 76 Distance Meter and a 200 foot Lufkin steel tap.

PERSONNEL: Bob Malotte and Jerry Swanson.

June 20, 1979

Jerry R. Swanson  
Deputy County Surveyor

Approved by: \_\_\_\_\_  
Edward A. McGinty, County Surveyor

