

FND 3/4" IRON BOLT WITH SQUARE HEAD 4" DEEP

SHULTZ ROAD

S 89°55'45" E 661.25
BASIS OF BEARING SEE R.S. 788

FND 3/4" IRON PIPE FLUSH
FND 1" IRON PIPE 8" DEEP

(a) POINT OF BEGINNING (b)

50.00 119.47
10.47
CENTER-EAST 1/16 CORNER

RESERVED FOR ROADWAY & UTILITY PURPOSES (EXISTING & FUTURE)

CIVIL AIR PATROL SITE
1.769 ACRES

SCALE 1" = 50'

MAP OF SURVEY FOR
MEDFORD-JACKSON COUNTY AIRPORT
OF
THE CIVIL AIR PATROL SITE,
LOCATED WITHIN THE
EAST HALF OF THE EAST HALF OF
SECTION 1, T37S, R2W,
W.M.
JACKSON COUNTY, OREGON

REGISTERED PROFESSIONAL LAND SURVEYOR

JERRY R. SWANSON
760

JERRY R. SWANSON
DEPUTY COUNTY SURVEYOR

JACKSON COUNTY RECEIVED
AUG 7 1979
SURVEYOR

- MONUMENT FOUND AS DESCRIBED
- SET 5/8" x 30" (a) OR 24" (b) REBAR EXPOSED 1-1/2" WITH PLASTIC CAP MARKED 'JACKSON C.S.'
- PROJECTED LEASEHOLD DESCRIBED CORNER SEE COUNTY SURVEYOR PROJECT FILE 79-17

BASIS OF BEARING: R.S. 788
SET-BACK REQUIREMENTS FROM RUNWAY BASED ON O.S. PROJECT NO. 77-4 & R.S. 6806
AUGUST 2, 1979
JACKSON COUNTY SURVEYOR'S OFFICE
MEDFORD, OREGON 97501

REC. (S 0°02'10" W, 1018.77 R.S. 788)
(S 0°01'39" W, C.S. PROJECT NO. 77-4 & R.S. 6806)

AIRPORT PRIVATE PROPERTY

N 0°02' E 444.45 (REC. N 0°01'39" E)

S 68°46' W 272.48

RESERVED FOR OTHERS

N 68°46' E 330.88
UNUSED LEASED AREA
EDGE OF PAVEMENT

PACIFIC FLIGHTS, INC.
SEE R.S. NO. 6806

FND 1" IRON PIPE EXPOSED 2"

SURVEY NARRATIVE TO
Comply with O.R.S. 209.250

Survey for: Medford-Jackson County Airport and
Civil Air Patrol

Survey by: Jackson County Surveyor's Office
County Courthouse
Medford, Oregon 97501

Survey Location: East One Half (E1/2) of the East One
Half (E1/2) of Section 1, Township 37
South, Range 2 West, Willamette Meridian,
Jackson County, Oregon.

Date: August 2, 1979

Purpose: To monument and describe a tract of land
to be used as the local Civil Air
Patrol Site at the Medford-Jackson
County Airport.

Basis of Bearing: Record Survey No. 788, bearing of the
Southerly right-of-way line of Shultz
Road, a County Road.

Basis of Survey: Monuments found and County Surveyor
Project No. 77-4 and Record Survey
No. 6806.

Procedure: The proposed site has been designated
in the overall Airport Layout Plan,
dated July 1978, for the Medford-
Jackson County Airport as the local
Civil Air Patrol site. Using this
plan as the guide and with discussions
with both airport and Civil Air Patrol
personnel, the tract was staked out
as shown on the accompanying map of
survey based upon surveys of records
shown above and monuments found in
the area. This project was authorized
by Edward A. McGinty, County Surveyor,
at the request of the Civil Air Patrol.

Reference: See County Surveyor Project No. 79-17.

Jerry R. Swanson
Deputy County Surveyor

