



**MAP OF SURVEY**  
 Located in Section 30, T37S, R2W,  
 W.M., Jackson County, Oregon.  
 for  
**T.FLATEBO AND K.C.WEAVER**

REGISTERED  
**PROFESSIONAL**  
 LAND SURVEYOR  
*Kurt C. Weaver*  
 OREGON  
 JULY 14, 1978  
 KURT C. WEAVER  
 1679

Basis of Bearing: SOLAR OBSERVATION  
 Ⓞ FD. JACKSON CO. BRASS CAP AS SHOWN.  
 ⊕ SET 2"x30" G.I.P w/A 21/2" BRASS CAP  
 SCALE: 1" = 400'  
 DATE: March 30, 1979.



## SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: T. Flatebo and K.C. Weaver  
P O Box 900  
Jacksonville, Oregon 97530

LOCATION: Located in Section 30, Township 37 South,  
Range 2 West of the Willamette Meridian,  
Jackson County, Oregon.

PURPOSE: To Subdivide Section 30 for control to be  
utilized in Deed retracement and future  
surveys.

PROCEDURE: Utilizing a Wild T-2 and an H.P. 3805 A  
EDM a series of closed traverses  
encompassing the controlling corners of Section  
30. The East and West 1/4 corners were set on  
a proportion basis after diligent search for  
original evidence of the corners was made,  
yielding no trace of original monuments or  
accessories.

The Section was subdivided in order to  
determine the position of the East line of  
Government Lots 2 and 3, which is the West  
line of Deed Record Vol 470, page 4.

SURVEYED BY: T. Flatebo and Associates, Inc.  
P O Box 900  
Jacksonville, Oregon

Date: March 30, 1979

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Kurt C. Weaver*

OREGON  
JULY 14, 1978  
KURT C. WEAVER  
1679

