

PCS 72+28.27

BIDDLE ROAD

AIRPORT PROPERTY

PRIVATE IRRIGATION DITCH

WIRE FENCE

EAST

188.16

P.O.B. - N.592.16 & E.823.71 FROM THE S 1/4 COR. OF SECTION 1, 37-2W (THIS COR. 4' E'LY OF R/W FENCE)

B.C.V.S.A. MANHOLE

TA = 79°59'
8° C.R.
f = 916.49
600' SPS
S = 24'00'

F.A.A. STORAGE SITE

0.500 ACRE

U/S TELEPHONE BOX

ROAD

ROAD

WIRE CHORD = N5°35'W, 207.67

287.08
S36°00'W

- FOUND 5/8" REBAR R/W MON. WITH METAL SIGN POST ONLY
- SET 5/8" REBAR WITH PLASTIC CAP MARKED 'JACKSON C.S.'

BASIS OF BEARING: SEE R.S. NO. 7936

PT 78+28.27

N10°44'41"E

UNIMPROVED

AIRPORT PROPERTY

SCALE 1" = 50'

PS 79+41.39

R/W



MAP OF SURVEY FOR

MEDFORD-JACKSON COUNTY AIRPORT

OF

AN F.A.A. STORAGE SITE,

LOCATED WITHIN

THE SW 1/4 OF THE SE 1/4 OF SECTION 1, T37S, R2W, WM, JACKSON CO., OREGON

AUGUST 1979

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 8, 1966 JERRY R. SWANSON 760

JERRY R. SWANSON DEPUTY COUNTY SURVEYOR

C.S. PROJECT 79-18

JRS

T37.2W, SEC 1D TL 800

17940

17940

SURVEY NARRATIVE

TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: Medford-Jackson County Airport and the F.A.A.

SURVEY BY: Jackson County Surveyor's Office
County Courthouse
Medford, Oregon 97501

SURVEY LOCATION: The Southwest Quarter (SW $\frac{1}{4}$) of the Southeast Quarter (SE $\frac{1}{4}$) of Section 1, Township 37 South, Range 2 West, Willamette Meridian, Jackson County, Oregon.

DATE: August 9, 1979

PURPOSE: To monument and describe a parcel of land to be used as an equipment storage site for the Federal Aeronautics Administration at the Medford-Jackson County Airport.

BASIS OF BEARING: See R.S. No. 7936, which utilized basis of bearing from R.S. 788.

BASIS OF SURVEY: Monuments found along the Easterly right-of-way line of Biddle Road, see R.S. 7434, "Biddle Road", Head Road to Airport Road Section, Drawing 9B-11-8 and direct tie to the South Quarter Section Corner of said Section 1, T37S, R2W, W.M., said corner being a brass cap set in a concrete post all within a monument case in the center of Table Rock Road.

PROCEDURE: Made bearing tie, located and tied down monuments as shown on map, allowed ten feet from a fence locating a private irrigation ditch, prepared the description and accompanying map. This survey authorized by Edward A. McGinty, County Surveyor.

REFERENCE: See County Surveyor Project No. 79-18.

Jerry R. Swanson
Deputy County Surveyor

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jerry R. Swanson
OREGON
JULY 8, 1966
JERRY R. SWANSON
760

JACKSON COUNTY
RECEIVED
AUG 10 1979
SURVEYOR

F 7940