



PLAT
SHOWING A SURVEY IN SECTION 26,
T 36 S, R 1 W, W.M., JACKSON CO., OREGON.

MAY 23, 1980 1"=1000'

- POINT FOUND AS NOTED
- 5/8" x 30" IRON ROD WITH CAP SET

MERIDIAN: SOLAR OBSERVATION.

REQUESTED BY: TERESA BEATTIE
 688 MANZANITA
 ROGUE RIVER, ORE. 97537

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

OREGON
 GERALD V. NYGREN
 AUGUST 22, 1975
 1035

JACKSON COUNTY
 RECEIVED
 JUN 3 1980
 SURVEYOR

NYGREN-ROGERS & ASSOCIATES
 PROFESSIONAL LAND SURVEYORS
 514 N.E. 7th STREET • PH: (503) 476-7034
 GRANTS PASS, OREGON 97526

8389

Nygren - Rogers & Associates

PROFESSIONAL LAND SURVEYORS
514 N.E. 7TH ST. - GRANTS PASS, OREGON 97526 - PHONE 476-7034

SURVEY NARRATIVE

Date: May 23, 1980

Surveyed for: Teresa Beattie
688 Manzanita
Rogue River, OR 97537

Location: In Section 26, Township 36 South, Range 1 West
of the Willamette Meridian, Jackson County, Oregon.

Purpose: To establish the Center Quarter corner.

Procedure: I set up a network of trilateration from which
I made long electronic distance meter (EDM) shots and multi
angles to tie in the four (4) Quarter corners.

Beginning at a point 3600 feet East of the East Quarter, I
shot a point near the East Quarter and the Center Quarter
and the South Quarter of the Section. Thence from the point
near the Center Quarter, I shot a point near the North
Quarter, thence to a point near the Northwest Quarter, thence
to a point near the West Quarter. From these points I
tied into each of the Quarter corners. I then crossed out
the Section by line intersection and set a 5/8" X 30" iron
rod with cap to mark the Center Quarter corner.

