



REGISTERED PROFESSIONAL LAND SURVEYOR

Darrel W. Edwards

OREGON JULY 6, 1958

DARREL W. EDWARDS 741

SURVEY FOR: E.C. BRITTSAN & WAYNE McKINTOSH		
SCALE: 1"=400'	APPROVED BY:	DRAWN BY:
DATE: JUNE 12, 1980		REVISED:
LOCATION: NW 1/4 SEC. 21, T.34 S., R. 1 E.W.M., IN JACKSON COUNTY, OREGON.		
● MONUMENT FOUND	() RECORD MEASUREMENT	DRAWING NUMBER
○ 5/8" STEEL PIN SET	--- FENCE LINE	

SURVEY NO. 8414

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250, OREGON REVISED STATUTES.

SURVEY FOR: E.C. Brittsan and Wayne McIntosh
539 1/2 Teresa Way 1953 Crowfoot Rd.
Central Pt, Or. Eagle Pt., Or,

LOCATION: In Sec. 21, T. 34 S., R. 1 E.W.M., in Jackson County, Oregon.

PURPOSE: To locate and monument property boundaries of Brittsan and McIntosh parcels and to locate the access road that serves the subject parcels.

PROCEDURE: Found brass caps at the NW, SE, NE and the West 1/4 corners of Sec. 21. Also found a 2 1/2" I.P. at the SW corner of the Section and a 5/8" steel pin set for the North 1/4 corner in R.S. 6143. Did not find evidence to reestablish the East or South 1/4 corners and therefore split the East and South lines of the Section equally. Subdivided the Section and set 5/8" steel pins, as shown on the accompanying plat. Blazed trees for the CW 1/16 corner as follows: a 5" oak bears S. 20° W. 7.40 feet; a 8" oak bears N. 73° West 3.70 feet. Blazed trees for the center 1/4 corner as follows: a 48" oak bears S. 58° W. 82.4 feet; a 10" pine bears S. 18° E. 35.0 feet.

BASIS OF BEARINGS: R.S. 6143

DATE COMPLETED: June 12, 1980.

Darrel W. Edwards
P.O. Box 801
Rogue River, Or. 97537
Ph: 582-3110

