

6 5
7 8
T38S, R1E
Fd. C.S. 1969 1" br. capped pipe

S 0° 01' 00" W
201.73

S 40° 25' 30" E
1128.77

S 40° 56' 10" E
1071.87

S 41° 08' 35" E
3038.69

S 68° 58' 50" E
572.81

S 0° 16' 55" E
905.47

S 89° 15' 45" W
2129.08

S 89° 15' 45" W
3076.66

S 89° 15' 10" W
1438.88

1/4 Sec. Cor.
Fd. C.S. 1975 1" br. capped pipe

7 18

PROPOSED

BOUNDARY

LINE

AGREEMENT

PROPOSED BOUNDARY

LINE AGREEMENT



SCALE 1" = 400'

Basis of Bearings: Solar Observ.


LEGEND

- o = Set 5/8" x 24" I. Pin (tagged R.L.S. 638)
- x-x-x = Existing fence

REGISTERED
PROFESSIONAL
LAND SURVEYOR

George Burrell

OREGON
JULY 10, 1964
GEORGE R. BURRELL
638



MAP OF SURVEY

Located in Sec.s 7 & 8 Twp. 38S, R1E
For: BARBARA DECKER
By: George Burrell, Surveyor 11/10/80

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Barbara Decker
3303 N. Valley View Rd.
Ashland, Oregon

PURPOSE: To monument and describe a line, located according to the clients instructions for the purpose of partitioning and conveying the Ben Dawson Estate property to his three heirs.

PROCEEDURE: A Solar observation was taken near the N.W. corner of section 8 for bearing control. The lines effecting the interior partitioning only were run and monumented as shown on the accompanying map, according to the clients instructions. A search was made for the S.W. and South 1/4 section corners of section 8, with negative results. As it was the original intent of the client to use the South boundary of section 7 and 8 as one of the division lines and inasmuch as the controlling section corners are lost, the line was run and monumented according to the clients instructions, as shown on the accompanying map, and a description was furnished for boundary line agreement purposes between the three heirs and other adjoiningers.

BY: George Burrell, Surveyor
1379 Brookdale Rd.
Medford, Oregon Nov. 10, 1980

REGISTERED
PROFESSIONAL
LAND SURVEYOR

George Burrell

OREGON
JULY 10, 1964
GEORGE R. BURRELL
638

JACKSON COUNTY
RECEIVED
DEC 9 1980
SURVEYOR