



SURVEY NO. 8650

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250, OREGON REVISED STATUTES

SURVEY FOR: Lois Hamm and Leigh Salsbury  
% Mary's Realty  
P.O. Box 163  
Rogue River, OR 97537

LOCATION: NW 1/4 of Sec. 2, T.36S., R.14W., W.M., in Jackson County, Oregon.

PURPOSE: To locate and monument SW and NE corners of Gov't Lot 4 and flag the approximate East and South boundaries thereof. Locate and monument property boundaries of two 5.00 acre parcels as shown on the accompanying plat.

PROCEDURE: Traversed between NW corner of Sec. 2 and North 1/4 corner of Sec. 2. Returned to NW corner of Sec. 2 and traversed South to the West 1/4 corner of said section.

From NW corner of Sec. 2 I surveyed S. 89°59'33"E. on true N/L of Sec. 2 a distance of 1316.48' and set 1/16 corner at proportioned distance; thence S. 0°13'51"W. along approximate E/L of Gov't Lot 4. Returned to NW corner of Sec. 2 and surveyed S. 0°13'51"W. on true W/L of Sec. 2 a distance of 1284.66' and set a 5/8" Steel Pin; thence S. 89°59'33"E. to the approximate SE corner of Gov't Lot 4. I then surveyed the two 5.00 acre parcels as shown on the accompanying plat.

I blaze trees as follows at the 1/16 corner A on the accompanying plat:  
6" W. Oak bears S 5°E, 26.3 feet  
6" W. Oak bears S 41°W, 38.1 feet

EQUIPMENT: Zeiss Th 43 Theodolite and Lietz Red-1 EDM

BASIS OF BEARINGS: R.S. 7765 (Plat of Heavenly Hills Subdivision)

DATE COMPLETED: Nov. 17, 1980

Darrel W. Edwards  
P.O. Box 801  
Rogue River, OR 97537  
Ph. 582-3110

