

SURVEY NO. 8819

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: McGrew Brothers Sawmill, Inc.
P.O. Box 610
Ashland, OR 97520

LOCATION: A portion of the Southeast one-quarter of
Section 14, Township 39 South, Range 1
East, Willamette Meridian, Jackson County,
Oregon.

PURPOSE: To survey and monument the two parcels as
shown on the attached map.

PROCEDURE: A search was made for the East one-quarter
corner and the Southeast corner of said
Section 14, but nothing could be found.
Since the Northeast corner of Government
Lot Number 3 was set on the East-West
one-quarter line during survey number
4847, I used said corner to determine the
center East one-sixteenth corner of said
Section 14. The angle between the North-
South one-quarter line and the South line
of said Section 14, as shown on survey
number 5661, was used to determine the
location of the East one-sixteenth corner
on the South line of said Section.

All traverses were run with a one second
Kern and a Hewlett Packard distance meter.

DATE: May, 1981

FRIAR-MOFFIT & ASSOCIATES
717 West 10th, Suite 1
Medford, OR 97501
Phone: 772-2782

