

SURVEY NO. 8957

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Vane Hoage
2799 Siskiyou Blvd.
Ashland, Oregon 97520


LOCATION: West one-half (1/2) of the West one-half (1/2)
of Section 24, Township 38 South, Range 3 East,
Willamette Meridian, Jackson County, Oregon

PURPOSE: To survey and monument the property per client's
request as shown on the attached map of survey


PROCEDURE: Using monuments that have been previously estab-
lished as shown on the attached map, and descriptions furnished by
the client, I determined the property lines by proportionate break-
down of the West one-half (1/2) of Section 24. The Northwest corner
of Section 24 falls in Howard Prairie Reservoir and its location was
determined as near as possible by using witness posts set by B.L.M.
to the North and to the East. A witness post was found to the South
to be 7.41 feet West and 65.61 feet South of its record position and
was not used in determining the location of the Northwest section
corner. I set 5/8 inch x 24 inch iron pins with kaps "D. McMahan
L.S. 1913" as shown on the attached map.

Basis of Bearing--B.L.M. records

July 27, 1981



Douglas C. McMahan



Douglas C. McMahan
Hoffbuhr/Bath & Associates, Inc.
219 North Oakdale
Medford, Oregon 97501