



A 26 inch diameter maple bears S 30° 58' W, 76.46 feet. No marks are visible on an open blaze. (Record/ Bureau of Land Management's 1976 survey, S 31° W, 116 links.)

An 18 inch fir bears N 65° 47' W, 31.60 feet. No marks are visible. (Record/ Bureau of Land Management's 1976 survey, N 68° W, 47.5 links.)


A 25½ inch cedar snag, 4 feet tall, bears N 4° 21' E, 168.24 feet. No marks are visible. (Record/ Bureau of Land Management's 1976 survey, N 4½° E, 254.5 links.)

Note: All trees measured were measured to the side center of the tree.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*John Scott Pierson*

OREGON  
JULY 14, 1978  
JOHN S. PIERSON  
1650



Survey No. 9012

SURVEY NARRATIVE TO COMPLY WITH ORS 209-250

For: Harry Stamper  
524 Granite Street  
Ashland, Oregon  
97520

By: John Pierson  
1807 East Main Street  
Ashland, Oregon  
97520

Purpose: To establish a new agreeable boundary between Harry Stamper (Tax lots 2201, 2204, 1300, 1200, NE $\frac{1}{2}$  of Section 17, Township 39 South, Range 1 East, Willamette Meridian) and Mark Cooper (Tax lot 2200, NE  $\frac{1}{4}$  of Section 17, Township 39 South, Range 1 East, Willamette Meridian.)

Location: The NE  $\frac{1}{4}$  of Section 17, Township 39 South, Range 1 East, Willamette Meridian, Jackson County, Oregon

Date: August 25, 1981

Basis of Bearing: Record Survey No. 8756  
(Solar Observation)

Procedure:

From points found from Record Surveys 8756, 7874, 6758, which for the most part harmonize, (see Record Survey 8756), I set monuments at agreeable locations as shown on the Map of Survey.

The Sectional corners used on this survey are two of the same monuments as used on Record Survey 8756. They are the NE corner of Section 17, and the East  $\frac{1}{4}$  corner of Section 17. They are as follows:

I held the pipe called for in the Bureau of Land Management's 1976 survey described as being the Northeast Section corner of Section 17, T. 39 S, R. 1 E, W.M., as found and referenced by C. Albert White in 1960. By record Survey No. 8239, surveyed in May of 1975, there is a possible corner location other than the one I used as described as at Northeast Section Corner of Section 17, T. 39 S, R. 1 E, W.M. I found a 2 $\frac{1}{2}$  inch outside diameter iron pipe with a chain link fence built over it. (The fence courses generally East-West) from which:

a granite outcropping, 5 feet long, 4 feet high, 3 feet wide bears N 74° 18' W, 12.83 feet marked "B + 0." (Record/ Bureau of Land Management's 1976 survey, N 74° 40' W, 19.3 links.)

The Northwest corner of Brown's house bears S 83° 56' E, 47.44 feet. (Record/ Bureau of Land Management's 1976 survey, S 83° 50' E, 72 links.)

At the  $\frac{1}{4}$  corner common to Sections 17 and 16, T. 39 S, R. 1 E, W.M., I found a 3 $\frac{1}{2}$  inch diameter brass cap marked as shown on the map, from which: