



See Narr  
 Fd 3/4" I. PIPE  
 Sur. No. 4686

9068

See Survey No 8301  
 2

COMPUTED FROM PREVIOUS SURVEY  
 1 = S76°13'10"W 355.45'  
 2 = S71°08'44"W 489.32'  
 3 = Arc 104.719', Radius 200', Delta 30°00'  
 4 = N78°51'16"W 55.98'

1324.73'  
 SURVEY NO 8301 N0°15'50" E

WEST (287.49 approx)  
 294.32'



REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Edward A. McGinty*  
 OREGON  
 JULY 10, 1953  
 EDWARD A. MCGINTY  
 301

SURVEY IN SE 1/4 SEC. 9, T. 35 S., R. 1 W., WM.  
 FOR: ALEXIS BOUTACOFF  
 79-18

BY EDWARD MC GINTY  
 P.O. BOX 1531  
 MEDFORD, OREGON  
 OCT. 11 1981

SCALE 1" = 100'  
 ● = 5/8" x 24" I. Pin

Sec 9 10  
 16 15

B-1

(Narr. attached)

35 1W 9

SURVEY NO. 9068

SURVEY NARRATIVE

Survey for: Alex Boutacoff  
16005 Hwy. 62  
Eagle Point, Or 97524

Survey by: Edward A. McGinty, RS  
P.O. Box 1531  
Medford, Or 97501

Location: Situated in the SE 1/4 of Sec. 9, T35S, R1W WM

Basis of Bearing: Determined from field traverse points along the center line and along Sec. line 9 and 10 on Survey No. 8301.

Precedence of Survey:

No attempt was made to confirm the location or accuracy of previous monuments set for the 1/16 corner as the client owns both sides of the line between Sec. 9 and 10, also the client is aware that no attempt was made to determine the location of the North and West boundry of tract, nor was any attempt made to determine the statute of any validity of adverse possession.

The purpose of this survey was to determine two lines and the approx. termination for boundary line adjustment for Parcel No. 1, shown on previous Major Partition, by changing its size and shape.

Monuments set being 5/8 in. X 24 in. iron pins, set approx. flush with the surface.

