

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250

OREGON REVISED STATUTES

Survey for: Norman Hay
7161 Crowfoot Road
Trail, Oregon 97541

Survey by : Charles H. Hurst
304 South Holly
Medford, Oregon 97501

Bearings : Data furnished by Hoffbuhr Surveying, Inc. pertaining to Survey No. 7244, i.e. a bearing from the east quarter corner of Sec. 2 to an adjacent transit station established during the course of said survey.

Purpose : To locate a portion of the $S\frac{1}{2}$ $N\frac{1}{2}$ $SE\frac{1}{4}$ of Section 3 on the basis of a description furnished by the client.

Procedure

Section subdivisional lines were computed on the basis of Survey No. 7244 coordinates, a procedure deemed financially advantageous by the client to preclude repetition of the work already performed by said survey.

The centerline location of Crowfoot Road was not of interest to the client. Accordingly, witness corners were set along the approximate easterly right-of-way based on the physical center of said road.


The $S\frac{1}{16}$ corner common to Sections 3/2, set during the course of Survey No. 3231, very closely agrees with the computed position and consequently was held as found.

No evidence of the $1/4$ corner common to Sections 3 and 10 was located. Accordingly, the proportionate corner position was monumented with a $3/4$ "x 30" iron pin firmly set with top projecting 5" from ground surface from which:

- A 9.2" White oak brs. N $89^{\circ}45'$ W 51.4 ft. dist. mkd. "1/4 S3 BT"
- A 9.1" White oak brs. S $55^{\circ}30'$ W 64.7 ft. dist. mkd. "1/4 S10 BT"

Distances measured to center.

November 20, 1981



Charles H. Hurst

