

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Edgar S. Cook
1350 East Nevada Street
Ashland, Oregon

BY: Boyden Surveyors
108 Mistletoe Street
Medford, Oregon

PURPOSE: To establish, describe and monument (with witness corners) the Westerly boundary of a 10+ acre tract, being the adjusted lot line as approved by the Jackson County Department of Planning and Development on January 25, 1982 (Re: File 81-120-LLA; 39-1E-2-233 and 400), being located in the Northwest Quarter of Section 2, Township 39 South, Range 1 East of the Willamette Meridian.

PROCEDURE: Utilizing E.D.M. equipment, traversed from the Northwest corner of said Section 2, through controls established on Filed Survey No. 7035, to and around the subject parcel.



Ties were made to monuments shown controlling the Westerly boundary of Filed Survey No. 5441 as shown on the annexed map.

The North and South boundaries of the subject tract were not precisely located on this survey, only to the degree of assuring that the subject tract described is in excess of 10 acres.

From said controls, set monuments at positions shown on the annexed map.

Basis of Bearings: The grid meridian utilized on Filed Survey No. 7035, rotated 01° 29' 10" counter-clockwise to establish true meridian for this survey.

April 7, 1982



39 1E 2