



**** RECEIVED ****
 Date 4/20/82 By SK
 This survey Consists of:
 / sheet(s) Map
 / page(s) Narrative
JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Edward A. McGinty
OREGON
JULY 10, 1953
EDWARD A. MCGINTY
301

SURVEY IN N.1/2 SEC. 32, T.37 S., R. 2W., W.M.
FOR: JACKSON COUNTY
SO.-3

BY: EDWARD MC GINTY
JACKSON CO. SUR.
COURT HOUSE
MEDFORD, OREG.
APRIL 1982

SCALE 1" = 50'
 ○ = 5/8" I. PIN FD.
 ▼ = 5/8" I. PIN SET

BASIS OF BEARING = & OF 6TH ST. (N22°42'50" E) RE:
SURVEY NUMBER 5280

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

SURVEY FOR: Jackson County Oregon

SURVEY BY: Jackson County Surveyor
Edward A. McGinty

BASIS OF BEARING: Sixth Street N22°42'50"E - Also see Survey No. 5280.

DATE: April 1982

LOCATION: North half of Section 32, T37S,R2W, Pool and Klippel Addition and the Official Plat of City of Jacksonville.

PURPOSE: To survey or resurvey a line for boundary line agreement and redivide Jackson County ownership.

PROCEDURE: The retracement of Survey Number 5280 and the monuments A, C and D substantially are unchanged and in close agreement with previous proposed boundary line agreement, however at point B, found a 5/8" I.Pin, N57°04'34"W, 0.53 ft. This was discussed with George Burrell (surveyor for No. 5280) and he indicated strongly that somehow someone may have moved his monument. (Note: According to Burrell, this iron pin was set inside a small shed at the time of his survey, which is now removed). From this data, I prepared a description for boundary line agreement.

With the redivision of Jackson County owned land and in compliance with the City of Jacksonville, partitioning ordinance of which the tentative partition final approval was on March 15, 1982; the tracts were recomputed from data obtained by field measurement.

The purpose of re-lotting the tax lots is for future planning and development of the Southern Oregon Historical Society.

All monuments found at the street centerline intersections are 5/8" I.Pins, except at the intersection of "C" Street and 8th Street which is a 1 1/4" I.Pin.

Monuments set on this survey are 5/8" x 30" I.Pins with plastic caps marked "Jackson C.S."

** RECEIVED **

Date 4/20/82 By SK

This survey Consists of:

1 sheet(s) Map

1 page(s) Narrative

JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Edward A. McGinty

OREGON
JULY 10, 1953
EDWARD A. MCGINTY
301

Jackson County Surveyor
SO-2